BANGALORE DIVISION.

ADVERTISEMENT.

The 16th May 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 10th June 1891, for constructing a Chemical Laboratory and Lecture Theatre at the Central College at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 10th June 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 12 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Chemical Laboratory and Lecture Theatre at the Central College at Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of Estimate.

Items.	Per.	Rate.	Quantity.	Cost.
Earthwork excavation in foundations	C. Yd.		354	
Stone in chunam foundation	C. Ft.		8,643	
Brick in chunam	do		27,838	
Do archwork	do		1,700	
Flooring with concrete	Sq.		58·28	
Do stone flagging	do		34·45	
Do asphalte over 4½ concrete	do		22·75	
Plastering with chunam	do		320·26	
Color washing	do		105·54	
Whitewashing	do		214·72	
Roofing terrace	do		49·43	
Iron trusses	No.		4	
Stone slabs dressed	S. Ft.		298	
Teakwood work with wood oiling	S. Ft.		905	
Planking (teakwood, thick)	Sq.		34·56	
Purlin angle iron ⅜"	lb.		50·27	
Zinc sheeting	Sq.		36·00	
Ridging	R. Ft.		72	
Gutterings	do		144	
Crestings, 7¾ high	do		144	
Brackets	No.		60	
Water spouts, iron (4" dia.) with shoe, &c.	R. Ft.		556	
Drains in connection with down pipes	do		92	
Pannelled doors	S. Ft.		504	
Glazed windows, &c. .. .. . :	do		14·81	
Painting doors and windows, &c. (2 coats)	Sq.		39·60	
Cornice work (2 feet)	R. Ft.		355	
Do (¾ do)	do		325	
Do (1½ do) or ornamental to archways, &c. ..	do		2,019	
Do over ventilators	do		54	
Do Buttresses	do		240	
Earth filling to basement	C. Yd.		616	
Teak ornamental arches to porch (18 × 10) including fittings ..	Each.		2	
Do in gables (30 × 15) do	do		2	
Iron finials to end of gables (5 feet high)	do		2	
Total...				
Contingencies at 5 per cent...				
Grand Total Rs...				

R. T. SCALDWELL,
Executive Engineer.